

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickwell Drilling Co.

Complete Address 706 4th National Bank Bldg Wichita Kansas

Lease Name Halley (HALLEY) Well No. -1-

Location N 1/2 S 1/2 SE Sec. 33 Twp. 24 Rge. 13 (E) (W) ✓

County Stafford Total Depth 4226

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Reese Raising Pulling Inc.

Address Box 1082 Great Bend, Kan. License No.

Operation Completed: Hour 10:30 Day 12 Month 6 Year 68

The above well was plugged as follows:

264 ft of 8 5/8 in surface pipe circulated with cement.
4226 ft of 5 1/2 in pipe banded up to 4100 ft and 5 sacks
of cement, mud up to 260 ft a plug, and 10 ft rock
bridges and 2 1/2 sacks of cement. Mud up to 140 ft.
10 ft rock bridges and 10 sacks of cement to surface.

Recovered 2100 ft of 5 1/2 in pipe

I hereby certify that the above well was plugged as herein stated.

INVOICE

Signed: R. L. Swain
Well Plugging Supervisor

DATE 6/14/68
4939-W