

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 14 1966

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Tennaco Oil Company

Complete Address: 2000 Classen Bldg., Oklahoma City, Oklahoma

Lease Name C. E. Kirkpatrick Well No. # 21

Location ~~SE SE~~ SWSWSE Sec. 34 Twp. 24 Rge. 13 (E) (W) W

County Stafford Total Depth 3962'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Burch Exploration

Address: 1011 Union Center Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 8:00AM Day 11th Month March Year 1966

The Above well was plugged as follows:

243' of 8 5/8" surface pipe, cement circulated with 225 sacks. 1st
cementing plug and 1/2 sack of hulls was pushed in fluid to 225', and
cemented with 25 sacks, through the drill pipe. Hole was filled with
drilling mud to 40', 2nd cementing plug, bridged with hulls on fluid
at 40', and cemented with 10 sacks to the base of the cellar. Rat
hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

corrected
inv. -
3/14/66

DATE 3/14/66
INV. NO. 2864-u