

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

REC 15 1966

12-15-1966

Operator's Full Name Hellar Drilling Company, Inc.

Complete Address: 1014 Union Center Bldg., Wichita, Kansas

Lease Name Halley "A" Well No. # 2

Location N/2 SE SW Sec. 34 Twp. 24 Rge. 13 (E) (W) W

County Stafford Total Depth 3892'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Hellar Drilling Company, Inc.

Address: 1014 Union Center Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 6:00AM Day 14th Month Dec. Year 1966

The Above well was plugged as follows:

248' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid
level in the hole was at 80', 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 230', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing plug
bridged with 1/2 sack of hulls on fluid at 40', and cemented with 10 sacks
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/15/66
INV. NO. 4463-W