

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-093-21246-00-00
Spot: NWNWSESE Sec/Twnshp/Rge: 28-22S-36W
1274 feet from S Section Line, 1275 feet from E Section Line
Lease Name: KLEEMAN Well #: 1-28
County: KEARNY Total Vertical Depth: 3020 feet

Operator License No.: 9152
Op Name: MAREXCO, INC.
Address: PO BOX 21598
OKLAHOMA CITY, OK 73156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3019	0	WITH 550 SX CMT
SURF	8.625	930		WITH 375 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/22/2016 10:30 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: ERIC GREEN Company: GREEN OILFIELD SERVICE Phone: (785) 678-2621

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/11/2016 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 50 SX CMT WITH 200# HULLS TO 2658'. DISPLACE TO 1800' & PRESSURE TO 500#. HOLDING. RUN TBG TO 1007' & CIRCULATE CMT TO SURFACE WITH 80 SX CMT. TOOH WITH TBG & TOP OFF WITH 15 SX CMT. PUMP 50 SX CMT DOWN THE ANNULUS TO 150 PSI.

Perfs:

Top	Bot	Thru	Comments
2646	2658		

**KCC WICHITA
FEB 24 2016
RECEIVED**

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL.

Plugged through: TBG

District: 01

Signed *Ken Jehlik*
512
(TECHNICIAN)

RECEIVED
FEB 17 2016
KCC DODGE CITY *MR*

Form CP-2/3
no
2-26-16