

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-23770-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 6-33S-3E
323 feet from S Section Line, 4706 feet from E Section Line
Lease Name: WAYNE Well #: 1
County: COWLEY Total Vertical Depth: 3297 feet

Operator License No.: 33185
Op Name: QUAIL OIL & GAS, LC
Address: 525 INDUSTRIAL DR. PO BOX K
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3200		
PROD	5.5	3295		150 SX
PROD	5.5	3300		
SURF	8.625	300		
SURF	8.65	327		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/20/2016 8:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: DARREN PATTERSON Company: QUAIL OIL & GAS Phone: (620) 539-0464

Proposed Plugging Method: AS PER KCC RULES & REGS / 75 SXS ON BOTTOM - 2910', OR 2 CIBP 3200' & 2910', CIRCULATE 380'-0'.

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 01/21/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 3250', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 75 SXS 60/40 POZMIX 4% GEL 3% CC & DISPLACED IN CASING. PULLED TBG @ 800'. TAGGED CEMENT PLUG @ 2487'. W/TBG @ 800', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 3% CC & DISPLACED IN CASING. SDON. PRESSURED CASING @ 200#, HELD OK. RIH ON WIRELINE PERFORATED SQUEEZE HOLES 380'-381'. SWEDGED INTO 5 1/2" CASING, CONSOLIDATED MIXED & PUMPED 125 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 1/21/2016 5:00 PM. 1/26/2016, CONSOLIDATED TOPPED WELL BACK TO SURFACE W/20 SXS 60/40 POZMIX 4% GEL. CONSOLIDATED CEMENT TICKET #51141, & 51142.

Perfs:

Top	Bot	Thru	Comments
3260	3264		CSG
2976	2982		CSG

2-11-2016
Received
KANSAS CORPORATION COMMISSION
FEB 11 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: COMPLIANCE/ 10 YEAR RULE

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

720
2-26-16
Form CP-2/3

✓