

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-083-21741-00-00  
Spot: NWNE Sec/Twnshp/Rge: 24-21S-25W  
1415 feet from N Section Line, 1762 feet from E Section Line  
Lease Name: EUGENE WITMAN Well #: 1  
County: HODGEMAN Total Vertical Depth: 4567 feet

Operator License No.: 30742  
Op Name: PALOMINO PETROLEUM, INC.  
Address: 4924 SE 84TH ST  
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1569		CEMENTED WITH 135 SX CMT. 15 SX CMT CIRCULATED WITH 15 SX CMT.
PROD	5.5	4564	0	WITH 175 SX CMT
SURF	8.625	217		WITH 160 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/22/2016 12:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: GLENN DINKEL Company: PALOMINO PETROLEUM Phone: (316) 799-1000

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 35 SX CMT & 150# HULLS. PULL TBG TO 1700' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF & TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/22/2016 3:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4432' & PUMP 35 SX CMT & 150# HULLS. PULL TBG TO 1710' & PUMP 170 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4486	4489		
4465	4478		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED  
FEB 23 2016  
KCC DODGE CITY

Signed

*Michael Maier*  
JA

Received

KANSAS CORPORATION COMMISSION  
(TECHNICIAN)

FEB 25 2016

CONSERVATION DIVISION  
WICHITA, KS

no  
2-26-16

Form CP-2/3