

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-083-21518-00-01  
Spot: NESWNENE Sec/Twnshp/Rge: 14-21S-23W  
4574 feet from S Section Line, 740 feet from E Section Line  
Lease Name: FRUSHER FARMS Well #: 1  
County: HODGEMAN Total Vertical Depth: 4600 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PC	4.5	1508		WITH 350 SX CMT
PROD	4.5	4600	0	WITH 175 SX CMT
SURF	8.625	226		WITH 160 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/17/2016 10:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: SCOTT BOEH Company: RITCHIE EXPLORATION Phone: (620) 617-4671

Proposed Plugging Method: SQUEEZE PERFS WITH 30 SX CMT & 100# HULLS. PLUG AT 1560' WITH CMT TO 0'. CHECK BACKSIDE WITH CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/17/2016 12:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4483' & PUMPED 35 SX CMT & 150# HULLS. PULLED TBG TO 1567' & PUMPED 125 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 25 SX CMT. TIED ONTO BACKSIDE. PUMPED 15 SX CMT. PRESSURED TO 300#.

Perfs:

Top	Bot	Thru	Comments
4519	4521		
4518	4520		
4513	4519		
4512	4518		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed

*Michael Maier*  
SA

(TECHNICAL) Received  
KANSAS CORPORATION COMMISSION

RECEIVED  
FEB 23 2016  
KCC DODGE CITY

FEB 25 2016  
CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

*no*  
*2.26-16*