

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-077-20894-00-01  
Spot: SENWSWSW Sec/Twnshp/Rge: 21-33S-6W  
662 feet from S Section Line, 4923 feet from E Section Line  
Lease Name: BASSFORD Well #: 2  
County: HARPER Total Vertical Depth: 5272 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	5033		500 SX
SURF	8.625	250		170 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/18/2015 12:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES Phone: (405) 429-6513

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 07/20/2015 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

UNABLE TO GET TO TD. MILLED AND FISHED FOR 30 DAY AND WAS ABLE TO GET TO 2840' DECIDED TO PLUG AT 2840'. RAN PERF GUN TO 2837' AND PERFED 4 HOLES. RAN TUBING TO 2837 AND PUMPED 75 SKS OF CEMENT. TAGGED CEMENT AT 2280' PERFED 4 HOLES AT 1260' AND RAN TUBING TO 1260' AND SPOTTED 75 SKS OF CEMENT. TAGGED CEMENT AT 855'. PERFED CASING AT 750', RAN TUBING TO 750 AND SPOTTED 50 SKS OF CEMENT. NO CEMENT TAG SPOTTED ANOTHER 50 SKS CEMENT, TAGGED CEMENT AT 550'. PERFED AT 300', RAN TUBING TO 300' AND CIRCUALTED CEMENT TO SURFACE UP ANNUALS AND INSIDE 5.5 CASING.

Perfs:


Top	Bot	Thru	Comments
4438	4443		CSG

Remarks: ORR INTER. CLASS C CEMENT

Plugged through: TBG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

KCC WICHITA  
FEB 22 2016  
RECEIVED

Form CP-2/3

220  
2-26-16