

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-30127-00-00  
Spot: S2SWSENW Sec/Twnshp/Rge: 29-34S-5E  
2914 feet from S Section Line, 3728 feet from E Section Line  
Lease Name: C M BOGGS TWIN Well #: 7  
County: COWLEY Total Vertical Depth: 2745 feet

Operator License No.: 34470  
Op Name: VICTORY MINERALS LLC  
Address: 11 N. SAINT JAMES PLACE  
EASTBOROUGH, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2710		125 SX
SURF	8.625	156		130 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/29/2016 8:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: LARRY ANSTINE Company: ANSTINE OIL CO. Phone: (620) 441-8706

Proposed Plugging Method: AS PER KCC RULES & REGS/ SAND @ 2650' W/5 SXS, CIRCUALTE 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE  
Date/Time Plugging Completed: 01/29/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2673', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 2% CC & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2296'. RIH ON WIRELINE PERFORATED SQUEEZE HOLES @ 300'-301'. RIH W/TBG @ 320', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 135 SXS 60/40 POZMIX 4% GEL, LAYED TUBING DOWN, SWEDGED INTO 5.5" CASING, MIXED & PUMPED 30 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. CEMENT TICKET #51147.

Perfs:

Top	Bot	Thru	Comments
2710	2740		OH

Received  
KANSAS CORPORATION COMMISSION  
FEB 11 2016  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

✓ JK

MO  
2-26-16