

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20364-00-00
Spot: SESWSW Sec/Twnshp/Rge: 11-23S-2W
330 feet from S Section Line, 4920 feet from E Section Line
Lease/Unit Name: HAURY Well Number: 3
County: HARVEY Total Vertical Depth: 2978 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

Conductor Pipe: Size feet: \$ 96.79
Surface Casing: Size 8.625 feet: 229 175 SX
Production: Size 5.5 feet: 2978 100 SX
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/25/2002 11:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.
Proposal Rcvd. from: EDDIE GRESSEL Company: GRESSEL OIL FIELD SERV Phone: (620) 463-5161

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: JACK LUTHI Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/25/2002 2:15 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Sanded bottom to 2892' and 5sxs of common. Perfed 5 1/2" @ 525' and 279'. Ran polly pipe to 525'. Pumped 35sxs let it set for 2 hours returned and ran polly pipe back to 279' circulate cement to surface.

RECEIVED
KCC DISTRICT #2
APR 05 2002
WICHITA, KS

Remarks: COPELAND CEMENT. 60/40 POZ 4% GEL.

Plugged through:

District: 02

Signed

Jack A. Luthi
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 4-08-02

WV. NO. 2002061618

DLOK