

To: 1040107
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-31-88
API NUMBER 15-185-21,883-0000

SE NE NE, SEC. 25, T 24 S, R 13 W/EX

4290 feet from S section line

330 feet from E section line

Lease Name Fox Well # 1-25 "B"

County Stafford 136.50

Well Total Depth 4200 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 327

TECHNICIAN'S PLUGGING REPORT

Operator License # 5020

Operator: Rine Exploration Company

Name & Address 300 West Douglas, Suite 645

Wichita, KS 67202

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 31 Month: 5 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4207' PBSD 4166' Perfs at 3868-76'

1st plug sand 50' above perfs with 4 sx cement on top of sand,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:15 p.m. Day: 31 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3818' and put 4 sx cement on top of sand
through bailer.

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100
lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 500 psi. and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 4 1/2" casing.

(If additional description is necessary, use BACK of this report)

INVOICED
did not observe this plugging.

DATE 6-22-88

INV. NO. 20939

Signed Stephen J. Pfeiffer
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
6-2-88
JUN - 2 1988

CONSERVATION DIVISION
Wichita, Kansas