

1 030392

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp, 8-27-57
SE SE NW, SEC. 23, T 24 S, R 13 W/R

2970 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Lease Name Tudor Well # 1 SWD

Operator: Kaiser-Francis Oil Company

County Stafford 138.58

Name & Address P. O. Box 21468

Well Total Depth 4264 feet

Tulsa, OK 74121-1468

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 3571 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 29 Month: March Year: 19 85

Plugging proposal received from John Glenn

(company name) Kaiser Francis (phone) 918-494-0000

were: 7" at 1965' 5 1/2" liner at 3840-4187' PBD 4264' Open Hole 4187-4264

1st plug sand back to 3800' and dump 7 sx cement on top of sand through bailer Pump through 8 5/8"

2nd plug at 960' with 70 sx cement

3rd plug at 330' with 472 sx cement to circulate to surface.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 5:00 pm Day: 29 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3800' and dumped 7 sx cement on top of sand through bailer, 2nd plug at 960' with 70 sx cement, 3rd plug at 330' with 472 sx cement to circulate to surface.

4-4-85

RECEIVED
STATE CORPORATION COMMISSION

APR 04 1985

Remarks: Recovered 1542' 8 5/8" casing. Used 60/40 Pozmix 2% gel by Sun.
(If additional description is necessary, use BACK of this form)
Wichita, Kansas

INVOICED

(If desired, ~~XXXXXX~~) observe this plugging.

DATE 4-9-85

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 7534