

To: 1 041166
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

15-185-21920-0800
API NUMBER 19- Docket #E-25,869
SE SW SE, SEC. 35, T. 24 S, R. 13 W/E
330 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31566
Operator: Benchmark Oil & Gas Corporation
Name & Address: 410 17th St., Ste. 1320
Denver, CO 80202

Lease Name Clowers Well # 2
County Stafford
Well Total Depth 4213 136.92 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 342

Abandoned Oil Well _____ Gas Well _____ Input Well SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 4:30 p.m. Day: 16 Month: 4 Year: 19 96

Plugging proposal received from David Brady

(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

were: 5 1/2" at 3827' w/150 sx cement, PBTD 4120', Perfs at 3811-15'

1st plug sand back to 3750' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30 p.m. Day: 16 Month: 4 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3750' and dumped 5 sx cement on top of sand

bridge through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs

hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 300 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

(did / did not) observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

INVOICED
DATE APR 24 1996
INV. NO. 45434

RECEIVED
KANSAS STATE CORPORATION COMMISSION
APR 17 1996