

To: 1 041165  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 185-<sup>21829</sup>-~~21,289~~-0000  
NE SW SE, SEC. 35, T 24 S, R 13 W/EX

TECHNICIAN'S PLUGGING REPORT 4-16

Operator License # 31566  
Operator: Benchmark Oil & Gas Corporation  
Name & Address: 410 17th St., Ste. 1320  
Denver, CO 80202

990 feet from S section line  
1650 feet from E section line  
Lease Name Clowers Well # 1  
County Stafford 134.42  
Well Total Depth 4136 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 333

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529  
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 16 Month: 4 Year: 19 96

Plugging proposal received from David Brady  
(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

Work: 5 1/2" at 4050' w/150 sx cement, PBTD 3630', Perfs at 3808-14, 3773-76, 3734-38, 3722-25, 3706-10, 3585-88'

1st plug sand back to 3525' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeiffer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part 4-23-1996 None

Operations Completed: Hour: 3 p.m. Day: 16 Month: 4 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3530' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 400 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

DATE APR 24 1996

INV. NO. 45433

Signed Steve Pfeiffer (TECHNICIAN)