

1 120468

9-13

15-185-22157-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,157-A
S/2 SW NW, SEC. 29, T. 24 S, R. 14 ~~W&E~~
2970 feet from S section line
4620 feet from E section line
Lease Name K.S.U. Well # 1
County Stafford 102.01
Well Total Depth 3139 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 348

TECHNICIAN'S PLUGGING REPORT

Operator License # 9482

Operator: National Petroleum Reserves, Inc.
Name & Address 250 N. Rock Road, #340
Wichita, KS 67206

Well Total Depth 3139 feet

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241

Address P.O. Box 819, Russell, KS 67665

Company to plug at: Hour: 1 P.m. Day: 12 Month: 9 Year: 19 90

Plugging proposal received from Bill Owen

(company name) Emphasis Oil Operations (phone) 913-483-3518

work: to fill hole with heavy mud and spot cement through drill pipe Lost circulation

1st plug at 1400' with 30 sx cement and check plug integrity before setting other plugs,

2nd plug at 950' with 50 sx cement, 3rd plug at 390' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 5 a.m. Day: 13 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 30 sx common cement 3% cc w/gibsonite at 1400',
let set 3 hours, attempt to tag plug failed.

2nd plug set bridge plug with D.P. at 955', pumped 50 sx cement at 950', hole stayed full,

3rd plug pumped 50 sx cement at 390', hole stayed full,

4th plug pumped 10 sx cement at 40',

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO.
(if additional description is necessary, use BACK of this form.)

INVOICED (1) / (1) observe this plugging.

DATE 9-25-90

Signed Duane Rankin
(TECHNICIAN)

INV. NO. 29426