


STATE OF KANSAS
 STATE CORPORATION COMMISSION
 (All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission,
 800 Bittling Building
 Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
 when reporting plug-
 ging off formations.

Stafford County. Sec. 23 Twp. 24 Rge. (E) 13 (W)
 Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SE
 Lease Owner Lario Oil & Gas Company
 Lease Name J. R. Morgan Well No. 4
 Office Address Wichita, Kansas
 Character of Well (Completed as Oil, Gas or Dry Hole) Dry
 Date, well completed May 20 1937
 Application for plugging filed May 25 1937
 Application for plugging approved May 27 1937
 Plugging Commenced June 23 1937
 Plugging Completed July 1 1937
 Reason for abandonment of well or producing formation Dry
 If a producing well is abandoned, date of last production 193
 Was permission obtained from the Conservation Division or its agents before plugging was commenced?
Yes




Locate well correctly on above
 Section Plat

Name of Conservation Agent who supervised plugging of this well C. T. Alexander
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				12 $\frac{1}{2}$ "	231'	
				6 5/8"	4097'	2101'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Dumped 300' of mud in bottom of hole, filled to 320' of top where a 12" bridge was set, then 25' of rock and cement and filled to top where a 5 sack cement cap was used.



(If additional description is necessary use BACK of this sheet)
 Correspondence regarding this well should be addressed to Lario Oil & Gas Company
 Address Union National Bank Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Leo Ross (employee of owner) or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo Ross
Union National Bank Building, Wichita, Kansas.
 (Address)

SUBSCRIBED AND SWORN to before me this 28 day of July, 1937.
 My commission expires June 17, 1940
Margaret Brown
 Notary Public.

15-185-10444-0000

LARIO - EMPIRE - ATLANTIC REFG.
J.R.Morgan No. 4.

SEC. 23 T. 24 T. 13W
NEo SE

Total Depth. 4111'
Comm. 4-21-37 Comp. 5-21-37
Shot or Treated.
Contractor. Broadwater Drlg.Co.
Issued. 7-3-37

County. Stafford



Elevation. EST 1970'

CASING:
12 1/2" 231'
7" 4095'

Production. Dry

Figures Indicate Bottom of Formations.

surface	43
shale & sand	231
red rock & shale	729
shale & shells	1253
shale & salt	1349
shale	1585
lime	1597
shale & lime	1674
lime	1706
shale & shells	1724
brkn lime	1804
shale & shells	1810
shale & lime	2027
shale	2098
lime	2135
shale & lime	2144
shale & shells	2241
shale	2320
lime	2332
shale	2347
shale & lime	2456
shale & shells	2781
shale	2786
lime	2811
shale & lime	2821
lime, shale & shells	2853
shale & lime	2907
lime, shale & shells	3025
lime	3102
shale & brkn limo	3161
shale & lime	3232
lime	3234
shale & lime	3325
lime	3366
shale & lime	3410
lime	3447
shale	3540
shale & lime	3649
lime	3678
shale	3716
lime	3732
shale	3745
shale & lime	3790
3790-3809	
shale & lime	3856
lime	3896
shale	3900
shale & shell	3934
lime & chat	4005
lime	4036
shale & lim	4062
shale	4097
lime HFW	4111
Total Depth.	

T. Siliceous 4101

PLUGGING
FILE SEC 23 T. 24 R. 13 W
BOOK PAGE 41 LINE 17