


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 23 Twp. 24 Rge. 13 (E) (W) x
Location as "NE/CNW/SW" or footage from lines 330' S - 660' E of W/4
Lease Owner Cities Service Oil Co.
Lease Name Benton Well No. #4
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 2-25-66 19____
Plugging completed 3-7-66 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4110' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded bottom from 3870' to 3580'. Mixed and dumped 5 sacks cement thru dump bailer. Pumped in 10 sacks jell and 70 sacks cement to base of cellar. Checked cement and was approximate 40' down. Topped out with 10 sacks cement to base of cellar.

RECEIVED
MAR 15 1968
CONSULTING ENGINEER

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14 day of March, 1966

My commission expires 21 October 1968

Sidney D. Miller
Notary Public.

WELL RECORD

Company Cities Service Oil Co. Well No. 4 Farm Benton
 Location 330' south & 660' east of W/4 Corner Sec. 23 T. 24 R. 13-W
 Elevation 1933 County Stafford State Kansas
 Drig. Comm. April 4, 1941 Contractor Hisson Drilling Company
 Drig. Comp. April 26, 1941 Acid 2000 gals. (April 28, 1941)
 T. D. 4110' Initial Prod. Depthograph Potential: 16,881 oil, no water, 2 1/2 hrs.

CASING RECORD:

8-5/8" @ 347' cem. 150 sx cement
 5-1/2" @ 4098' cem. 185 sx Lone Star

FORMATION RECORD:

sand 0-170
 red bed 187
 red bed, shale & shells 347
 shale & shells 785
 red bed 1100
 shale & salt 1343
 shale & shells 1707
 broken lime & shale 1796
 lime 1835
 sand & shale 1928
 broken lime & shale 2089
 shale & shells 2110
 lime 2167
 lime & shale broken 2263
 broken lime & shale 2364
 lime broken 2478
 lime & shale 2666
 broken lime & shale 2782
 shale 2829
 lime 2870
 shale & lime 2950
 broken lime & shale 3031
 shale 3072
 lime 3223
 broken lime & shale 3278
 lime 3442
 shale 3549
 lime 3711
 lime cored (rec. 4') 3719
 lime 3879
 shale 3895
 chert 3917
 shale 3931
 chert 3949
 shale & chert 3965
 chert 4005
 shale 4011
 chert 4016

shale with chert streaks 4037
 lime & chert 4075
 shale 4109
 lime 4111
 4111 Rot. TD = 4099 SIM
 dolomite 4110 T. D.

Corr. Top Arbuckle 4097
 Penetration 13
 Total Depth 4110

Fillup: 1700' oil in 2 1/2 hours
 2000' oil in 3 1/2 hrs.
 3000' oil in 5 1/2 hrs.
 4000' oil in 8 hrs.

Syfo: 500' OK
 1280' OK
 1530' OK
 1750' 1°
 2000' 0°
 2250' 1°
 2500' 1°
 2750' 1°
 3000' 1°
 3250' 1°

STAFFORD COUNTY, KANSAS

JAN 31 1960

CITIES SERVICE OIL CO.