

15-185-01477-0002

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER TUDOR
LEASE NAME Tetor #1
WELL NUMBER SE SE NW

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line
 Ft. from E Section Line

SEC. 23 TWP. 24s RGE. 13w (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 3/22/85

Plugging Completed 3/29/85

LEASE OPERATOR Kaiser-Francis Oil Co.

ADDRESS Box 21468, Tulsa, Ok. 74121

PHONE#(918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4260'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				16"	230'	none
				8 5/8"	3571'	1216'
				7"	1950'-3849'	none
				5 1/2"	3840'-4187'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3150' & 7 sacks cement. Shot pipe at 1916', 1712', 1517', Pulled 3 joints, pip started flowing. Shot pipe at 1326' & pulled 12 joints. Pumped 70 sacks cement at 900', pulled 21 joints to 300', & pumped 430 sacks, pulled 4 joints & pipe hung up, turned pipe with tongs until it screwed loose two joints down, pulled 2 joints. (42 joints) Left last (if additional description is necessary, use BACK of this form.) 100' in hole.

Name of Plugging Contractor Kelso Casing Pulling License No. RECEIVED 6050

Address Box 347, Chase, Ks. 67524 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss. APR 08 1985

R. Darrell Kelso (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 4th day of April, 1985

Irene Hoover
Notary Public

My Commission Expires:

