

15-185-00555-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Major Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County, Sec. 24 Twp. 24 Rge. 13 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW/NW/NE
Lease Owner Burch Drilling Company
Lease Name McMillan Well No. #1
Office Address 1758 North Main, Russell Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed Yes 19____
Application for plugging approved Yes 19____
Plugging commenced 6-13 19 57
Plugging completed 6-18 19 57
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. R.M. Brundedge
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4160' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		3,338'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging started 6-13-57. Measured into TD 4160'. Plugged off bottom with sand to 3730' and dumped 4 sacks cement with bailer. Shot 4 1/2" casing at 3338'. Pumped in 15 sacks of mud and 80 bbl oil. Pipe started. Pulled casing to 1200'. Pumped in 15 sacks aquagel mud. Pulled 4 1/2" casing to 270'. Pumped in 50 sacks cement. Pulled pipe out of hole. Set permanent rock bridge at 20' and capped well with 5 sacks cement. Well plugging finished 6-18-57.

6-20-1957

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1957

CONSERVATION DIVISION
OFFICES

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kans
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of June, 19 57.

Betty S. Edman
Notary Public.

My commission expires November 8, 1960.

PLUGGING
FILE SEC 24 T 24 : 13W
BOOK PAGE 19 LINE 4

DRILLERS LOG

MGMILLAN #1
NW NW NE sec. 24-24-13W,
Stafford County, Kansas

Elevation: 1903' KB
Comm: 5-8-57
Comp: 5-23-57
Surface: 8 5/8" @ 220' w/175 sx.
4 1/2" @ 3845' w/100 sx.
Result: D & A

Operator: Burch Drilling Co., Inc.
Contractor: Burch Drilling Co., Inc.

Tops:

215	Sand & Red Bed	Heebner	3368
1000	Shale, Shells, Red Bed	Douglas	3406
1575	Shale & Limestone	Brown Lime	3514
3465	Lime & Shale	Lansing	3545
3765	Lime	Viola	3923
3907	Shale & Lime	Simpson shale	4053
3944	Lime - Shale Cherty	Arbuckle	4111
4005	Chert Lime	RTD	4160
4023	Cherty Dolomite		
4049	Cherty Lime		
4107	Lime, Shale, Sand		
4131	Lime		
4160	Lime (Arb)		
4160	RTD		

BURCH DRILLING CO., INC.

By: Earl M. Burch
Earl M. Burch
President

State of Kansas)
) ss:
County of Sedgwick)

Before me the undersigned, a Notary Public, within and for said County and State, on this 6th day of June, 1957, personally appeared Earl M. Burch, President of Burch Drilling Co., Inc. to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

Subscribed and sworn to before me this 6th day of June, 1957.

My commission expires: 6-13-59.

Betty Spriggs
Notary Public

RECEIVED
STATE CORPORATIONS COMMISSION

JUN 12 1957

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 24 T 24 R 13W
BOOK PAGE 19 LINE 4