

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

21829
API NUMBER 15-185-21,289-0000

LEASE NAME Clowers

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 35 TWP. 24 RGE. 13 (EAK)(M)

COUNTY Stafford

Date Well Completed

Plugging Commenced 4-10-96

Plugging Completed 4-16-96

TYPE OR PRINT
NOTICE: Fill out complotoly
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Benchmark Oil & Gas Corporation

ADDRESS 410 17th Street, Ste. 1320

PHONE/(303) 595-9251 OPERATORS LICENSE NO. 31566

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4136'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
KANSAS CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	333'	none
				5 1/2"	4050'	2613'

APR 19 1996
CONSERVATION DIVISION
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s
Plugged off bottom with sand to 3530' and 5 sacks cement. Shot casing at 2800' and 2610'
Pulled casing, Pumped 300# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls,
release plug, pumped 125 sacks cement (60/40 POZMIX 6% gel) 400# Max. Shut in 150#.
Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Benchmark Oil & Gas Corporation -Denver, Co.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact
statements, and matters herein contained and the log of the above-described well as filed t:
the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 18th day of April, 19 96

[Signature]
Notary Public

My Commission Expires:

