

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

FORMATION PLUGGING RECORD

**Strike out upper line
when reporting plug-
ging off formations.**

NORTH

**Locate well correctly on above
Section Plat**

Name of Conservation Agent who supervised plugging of this well Mr. C. T. Alexander, Great Bend, Kansas
Producing formation Arbuckle Lime Depth to top 4179' Bottom 4234' Total Depth of Well 4234' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

The hole was filled with heavy mud to within 270' of top where a wood plug was set and cemented with 15 sacks of cement. The hole was then filled with heavy mud to within 26' of top where a wood plug was set and cemented with 10 sacks of cement. The 10-3/4" OD casing was cut off and a steel cap welded thereon 3' below the ground level.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mr. F. L. Dunn
Address R. F. D. #4, Lyons, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
F. L. Dunn (employee of owner) or (owner of

F. L. Dunn (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

R. F. D. #4, Lyons, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of March, 1943

My commission expires... Oct. 21st, 1944

.....
Notary Public.

W E L L L O G

G. L. Jones Well No. 1

Spudded: February 26, 1943
 Drilg. Completed: March 19, 1943
 Date Plugged: March 19, 1943

Loc: 330' N & 330' W of S/4
 corner of Sec. 36, T24N, R15W,
 Stafford County, Kansas

FROM	TO	FORMATION	FROM	TO	FORMATION
0	120	Surface clay	2405	2500	Lime & shale
120	290	Shale & shells	2500	2690	Broken lime & shale
290	715	Red bed & shale	2690	2995	Broken lime
715	745	Anhydrite	2995	3020	Lime & shale
745	750	Shale & shells	3020	3365	Lime
750	1095	Sand & shale	3365	3615	Lime & shale
1095	1115	Shale & shells	3615	3945	Lime
1115	1315	Salt & shells	3945	4118	Sand & chert
1315	1590	Shale & shells	4118	4155	Lime
1590	1715	Sand & shale	4155	4185	Lime & shale
1715	2025	Lime & sand	4185	4234	Lime
2025	2300	Lime & shale	4234'		Total depth in the
2300	2405	Shale & shells			Arbuckle lime formation

Elevation 1910'

Run 230' of 10-3/4" OD 22# 3-Ga. Armac spiral weld casing; set at 230';
 cemented with 225 sacks of cement.

Top of Anhydrite 715'

Top of Topeka Lime 3000'

Top of Lansing Lime 3592'

Top of Viola Lime 4007'

Top of Simpson Sand 4115'

Top of Arbuckle Lime 4172'

Cored from 4183' to 4198' - recovered 9' of core - no show of oil.
 Deepened to 4234' - no show of oil - conditioned hole to plug.

Plugged and abandoned March 19, 1943.

Total Depth - 4234' in Arbuckle Lime.

Note: All above footages are calculated from the ground level.

I, the undersigned, being first duly sworn upon oath, state that
 this Well Record is true, correct and complete according to the records of
 this office, and to the best of my knowledge and belief.

J. L. Dumas - Superintendent
 Name and title of representative of company

Subscribed and sworn to before me this 24th day of March, 1943.

My Commission expires October 21st, 1944

Louis M. Guire
 Notary Public

FLD-RDE 3/24/43

LPC (5)

Corporation Commission (1)
 Plains Exploration Company (1)
 Stanolind Oil & Gas Company (1)
 File (1)

