


15-185-30072-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Stafford County, Sec. 29 Twp. 24 Rge. (E) 14 (W)  
Location as "NE/CNW/SW" or footage from lines C NE NE  
Lease Owner Abercrombie Drilling, Inc.  
Lease Name DeBUSK Well No. 1  
Office Address 801 Union Center, Wichita, Kans. 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed July 3, 19 65  
Application for plugging filed verbally July 3, 19 65  
Application for plugging approved verbally July 3, 19 65  
Plugging commenced July 3, 19 65  
Plugging completed 2:30 July 4, 19 65  
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes

Name of Conservation Agent who supervised plugging of this well Elbing, Pratt, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 3870 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 253    | None       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 240'.  
Set 1st plug at 240' w/ 1/4 sk hulls & 25 sx cement  
Filled hole with heavy mud to 40'  
Set 2nd plug at 40' w/ 1/4 sk hulls & 10 sx cement  
Put 2 sx cement in rat hole.

7-8-1965

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.  
Address 801 Union Center, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick  
Mildred Saxton (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Mildred Saxton  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of July, 19 65

My commission expires June 16, 1967.

Leah Faye Hafke  
Leah Faye Hafke Notary Public.

CONTRACTOR'S WELL LOG

COMPANY: Abercrombie Drilling, Inc.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 FARM: DeBUSK #1  
 LOCATION: C NE NE Sec. 29-24-14W  
 Stafford County, Kansas  
 COMMENCED: June 25, 1965  
 COMPLETED: July 3, 1965

|      |      |                    |
|------|------|--------------------|
| 0    | 80   | Sand               |
| 80   | 263  | Shale              |
| 263  | 380  | Shale              |
| 380  | 932  | Red Bed            |
| 932  | 952  | Anhydrite          |
| 952  | 1545 | Shale              |
| 1545 | 1785 | Shale              |
| 1785 | 1875 | Lime & Shale       |
| 1875 | 3320 | Shale & Lime       |
| 3320 | 3414 | Lime               |
| 3414 | 3559 | Lime & Shale       |
| 3559 | 3606 | Lime               |
| 3606 | 3815 | Lime & Shale       |
| 3815 | 3870 | Lime               |
|      | 3870 | Rotary Total Depth |

Set 8-5/8" surface casing at 253' w/165 sx cement, 3% calcium chloride.

DRY & ABANDONED

|                     |            |                     |
|---------------------|------------|---------------------|
|                     | ELEVATION: | 1977' D. F. & K. B. |
|                     |            | 1971' Ground Level  |
| TOPS: Heebner       | 3551'      | (-1574)             |
| Toronto             | 3568'      | (-1591)             |
| Douglas             | 3587'      | (-1610)             |
| Brown Lime          | 3696'      | (-1719)             |
| Lansing/Kansas City | 3715'      | (-1738)             |

RECEIVED  
STATE COMMISSION

JUL 8 1965

CONSERVATION DIVISION  
WICHITA, KANSAS

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, Mildred Saxton, do hereby certify that the above and foregoing is a true and correct copy of the log of the DeBUSK #1, C NE NE, Section 29-24-14E, Stafford County, Kansas, as reflected by the files of Abercrombie Drilling, Inc.

*Mildred Saxton*

Mildred Saxton, Secretary

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 7th day of July, 1965.

*Leah Faye Hefke*

Leah Faye Hefke, Notary Public

My commission expires June 16, 1967.