

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-185-21,883-0000 (of this well) 6/88  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Rine Exploration Company OPERATORS LICENSE NO. 5020

ADDRESS Suite #645, 300 W. Douglas, Wichita, KS 67202 PHONE # (316) 262-5418

LEASE (FARM) Fox WELL NO. #1-25 "B" WELL LOCATION SE $\frac{1}{4}$  NE $\frac{1}{4}$  NE $\frac{1}{4}$  COUNTY Stafford

SEC. 25 TWP. 24S RGE. 13 (~~E~~) (W) TOTAL DEPTH 4200' PLUG BACK TD 4166'

Check One:

OIL WELL X GAS WELL        D & A        SWD or INJ WELL        DOCKET NO.       

SURFACE CASING SIZE 8 5/8" SET AT 327' KB CEMENTED WITH 200 SACKS

CASING SIZE 4 1/2" SET AT 4207' CEMENTED WITH 200 SACKS

PERFORATED AT 3868' - 3876' / 2 shots per foot.

CONDITION OF WELL: GOOD X POOR        CASING LEAK        JUNK IN HOLE       

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Bottom Plug: fill casing with sand up to 3860', then dump 4 sacks cement with bailer on top.

Top Plug: Squeeze down 8 5/8" - 4 sacks hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, 8 5/8" plug and 125 sacks cement on top.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes - filed  
(If not, explain) 01/19/84

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN To be arranged by Kelso at earliest date.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

M. Bradford Rine PHONE # (316) 262-5418

ADDRESS Suite #645, 300 W. Douglas, Wichita, KS 67202-2904

PLUGGING CONTRACTOR Kelso Casing Pulling, Inc. LICENSE NO. #6050 6/88

ADDRESS Box #347, Chase, KS 67524 PHONE # (316) 938-2457

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: M. Bradford Rine

(Operator or Agent)

(M. Bradford Rine)

DATE: 04/11/88

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
APR 14 1988

4-14-88

State of Kansas



## Kansas Corporation Commission

MIKE HAYDEN  
KEITH R. HENLEY  
RICH KOWALEWSKI  
MARGALEE WRIGHT  
JUDITH MCCONNELL  
FRANK A. CARO, JR.

GOVERNOR  
CHAIRMAN  
COMMISSIONER  
COMMISSIONER  
EXECUTIVE DIRECTOR  
GENERAL COUNSEL

CONSERVATION DIVISION  
SHARI M. FEIST, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

THIS NOTICE

JUL 14 '88

EXPIRES

April 14, 1988

### WELL PLUGGING NOTICE

Fox #1-25 B  
SE/4 NE/4 NE/4  
Sec. 25-24S-13W  
Stafford County

Rine Exploration Company  
300 W. Douglas, Ste. 645  
Wichita, KS 67202


Gentlemen: .

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

  
Shari Feist  
Director  
State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760