

15-167-00516-0000
WELL PLUGGING RECORD

Give All Information Completely

Take Required Affidavit

Mail or Deliver Report to:

**Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas**

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

NORTH

***Locate well correctly on above
Section Plat**

Russell County. Sec. **31** Twp. **15** Rge. **15** (E) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines.....NE of SW of SW

Lease Owner.....Kiowa Drilling Company, Inc......

Lease Name DeWald Well No. 1

Office Address.....717 Union National Bank Bldg. Wichita 2, Kansas.....

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date, well completed.....Jan. 16.....1945

Application for plugging filed Jan. 16 1945

Application for plugging approved Jan. 16 1945

Plugging Commenced	Jan. 17 at 12:30 A.M.	1945
--------------------	-----------------------	------

Plugging Completed.....Jan. 17 at 8:00 A.M.....1945.....

Reason for abandonment of well or producing formation.....Dry.....

If a producing well is abandoned, date of last production.....19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well..... H. W. Kerr

Producing formation None Depth to top 0 Bottom 0 Total Depth of Well 3477 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Circulated heavy Mud every 300 ft. thru drill pipe
Placed Bridge and Plug at 600 ft. Mixed and dumped thru drill pipe back to
540 ft. Heavy Mud from 540 ft. to 15 ft. Mixed and dumped 5 Sax Cement
from 15 ft. to bottom of cellar

(If additional description is necessary, use **BACK** of this sheet)

Correspondence regarding this well should be addressed to Kiowa Drilling Company, Inc.

Address.....717 Union National Bank Bldg.,.....Wichita 2.....Kansas.

STATE OF Kansas COUNTY OF Sedgwick ss

Perry A. Thayer (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

717 Union Nat'l Bank Bldg. Wichita 2, Kans.

(Address)

SUBSCRIBED AND SWORN to before me this 29th day of January, 19 45

November 20, 1948

Notary Public.

WELL LOG

KIOWA DRILLING COMPANY

723 UNION NATIONAL BUILDING

WICHITA, KANSAS

DISTRICT _____ OWNER Kiowa Drilling Co. et al FARM De Wald WELL No. _____
NE SW SWLOCATION: Section 31 Township 15S Range 15W County Russell State Kansas

CASING RECORD:

Size <u>8 3/8</u>	O. D.	Weight _____	lbs.	Amount <u>959</u>	ft.	Cemented <u>100</u>	#	Sacks	Kind Cement <u>Fulk</u>
Size _____	O. D.	Weight _____	lbs.	Amount _____	ft.	Cemented <u>100</u>	#	Sacks	Kind Cement <u>Lone Star</u>
Size _____	O. D.	Weight _____	lbs.	Amount _____	ft.	Cemented <u>100</u>	#	Sacks	Kind Cement <u>Calcium Chloride</u>

FORMATION RECORD:

0 to 96 Surface clay and shale
 340 Shale
 351 Iron
 420 Shale
 370 Sand
 665 Shale and Red Bed
 840 Shale
 930 Shale and shells
 954 Red Rock
 959 Anhydrite
 1335 Shale and Red Bed
 1400 Shale and shells
 1600 Shale and salt
 1650 Shale and lime
 2105 Lime
 2250 Lime and sandy shale
 2800 Lime and shale
 3382 Lime
 3460 Conglomerate
 3477 Arbuckle water T.D.
 Plugged and Abandoned

I hereby certify that this is a true
and correct log.

Kiowa Drilling Company, Inc.

By _____

Vice President

Subscribed and sworn to before me this
22nd day of January 1945.

Notary Public

My Commission expires November 20, 1948.

31 15 15W
2 21