


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Trego County. Sec. 6 Twp. 14 Rge. 21 E/W
Location as "NE/CNW1SW1" or footage from lines
SE SE NW

Lease Owner Don E. Pratt Oil Operations
Lease Name Kastnor #1 Well No. _____
Office Address Hays, Kansas 67601
Character of Well (Completed as Oil, Gas or Dry Hole) _____

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 10/18/76 _____ 19____
Plugging completed 11/19/76 _____ 19____
Reason for abandonment of well or producing formation
depleted

If a producing well is abandoned, date of last production
_____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? _____ yes

Name of Conservation Agent who supervised plugging of this well Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4133
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	255	none
				4 1/2"	4128	3227'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Sanded back to 4000' and ran 3 sacks cement, loaded hole. Shot pipe at 3211', pulled
88 joints. Pumped 3 sacks hulls, 70 sacks cement, 5 sacks gel, 1 sack hulls and 60
sacks cement.

PLUGGING COMPLETE.

NOV 24 1976
11-24-76

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) _____
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of November, 19 76

My commission expires _____



Notary Public.

Don Pratt

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas

15. 195. 01024. 00. 01

COPY

Company- DEEP ROCK
Farm- Kastner

No. 1


SEC. 6 T. 14 R. 21W
SE SE NW

Total Depth. 4133'
Comm. 7-25-53
Shot or Treated.
Contractor.
Issued. 5-29-54

Comp. 8-10-53

County Trego

KANSAS



CASING:
10 3/4" 255' w/225 sx com.

Elevation. 2257'

Production. Dry

Figures Indicate Bottom of Formations.

surface-clay	40
shale-shells	605
sand-shale-shells-	1135
sand	1380
shale-shells	1660
Anhydrite	1708
shale-red bed	1915
shale	2115
shale-shells	2225
lime	2300
lime-shale	2400
lime	3125
lime-shale	3615
lime	3873
shale-conglomerate	3928
shale-lime	4008
lime	4063
lime-shale-chert	4110
Arbuckle	4128
Arbuckle	4133
Total Depth	

"Owwo"

Don E. Pratt
#1 Robinson
D&A/ARB

NEW INFO: Re-entered 10/8/75; set 4 1/2" 4128/175sx
mict-co, pf (lkc) 16/4032-36, swb dwn 7 swb est 4
boph (notime) onfu 3000'o, Nw/48hrs, nat, swb 49 Bo +
Some sd, ac 4000 mca, pf (cher) 16/4032-36, ac 600,
swb dwn & rec 1d, swb 2 1/3 boph, Nw/4hrs, fu 1925'o,
nw/36 hrs, pop, p decr to 7 bopd, nw, D&A

RECEIVED
STATE CORPORATION COMMISSION

OCT 04 1976

CONSERVATION DIVISION
Wichita, Kansas

TOPS: Scout	
Anhydrite	1660
Hoebner	3588
Toronto	3608
Base Kansas City	3867
Marmaton	3963
Basal Penn. Sand	4027
Arbuckle	4077