

CHERRY DRILLING CO., INC.
102 Insurance Bldg.
WICHITA 2, KANSAS
HO 4-5769

ROTARY DRILLING LOG

Lease: Hertzler

Company: Cherry Drilling Co., Inc.
102 Insurance Bldg.
Wichita, Kansas

Well: No. 1

Location: C s/2 N/2 NW
Sec. 13-23S-2W
Harvey Co., Kansas

Contractor: Cherry Drilling Co., Inc.

Geologist: W. Pat Simmons
1801 Porter
Wichita, Kansas

Elevation: 1450 KB
1447 DF
1444 Gr

Surface Pipe: Run 11 Jnts. Used 8 5/8"
Surface Pipe. 228.79' overall
less threads. Cemented with
160 sacks cement, 2% c. c.

Well Commenced: 4-16-57
Under Surface 4-17-57
Well Completed: 4-28-57

Casing: Dry Hole. Filled hole to 226' with
mud, built solid rock bridge @ 226'
to hold wt. of d.p. with 5 sacks
cement to bottom. Displace 5 sacks
cement through 7 Jts. Dp Built top
Bridge.

0-340		2540-2620	Shale and Lime
340- 500	Lime	2620-2955	Lime
500-520	Lime	2955-3150	Lime and Chert
520- 580	Shale and Lime	3150-3180	Chert, Lime, Shale
580- 660	Lime	3180-3205	Lime, Sand
660 -880		3205-3295	Lime
880-1075	Lime	3295-3410	Lime, Chert
1075-1120	Lime, Sand	3410-3430	Lime
1120-1350	Shale, Shells		
1350-1715			
1715-2420	Shale, Lime		
2420-2540	Lime, Sand		

T. D. 3430

GEOLOGIST'S TOPS

Heebner	2120	Mississippi Chert	2980
Brown Lime	2353	Mississippi Dolomite	3005
Lansing	2364	Kinderhook	3298
Base K.C.	2745	Misener	3308
Congl.	2978	Hunton	3311
		Maquoketa	3375
		Viola	3419

R. T. D. 3430

The above is a true and correct log to the best of my knowledge.

Subscribed and sworn to before me on this 30th day of April, 1957.
My commission expires October 24, 1960.

Maxine Condon
Notary Public

PLUGGING

MAY 4 1957

FILE SEC. 13 T. 23 R. 2W
BOOK PAGE 10 LINE 22

CON. DIVISION