


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD



Harvey County, Sec. 11 Twp. 23S Rge. 2 W (W)  
Location as "NE/CNW/SW" or footage from lines SW SW NW  
Lease Owner O. A. Sutton  
Lease Name Stauffer Well No. 1  
Office Address 407 Insurance Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 17 19 60  
Application for plugging filed " " 19 "  
Application for plugging approved " " 19 "  
Plugging commenced " " 19 "  
Plugging completed " " 19 "  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3417 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	206'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with mud from 3417 to 210 ft. Set Plug #1 with 1/2 sack hulls and 25 sacks cement. Filled with mud from 160' to 40'. Set Plug #2 at 40' with 1/2 sack hulls and 10 sacks cement. Put 2 sacks of cement in rat hole. Plugged at 3:30 P.M. March 17, 1960 by Cecil Jones, McPherson, Kansas.

3-23-1960

IRIE L...  
STATE CORP...  
MARCH 23 1960  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor J. S. Sutton & Sons  
Address 313 Insurance Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
R. G. Brooks (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. G. Brooks  
407 Insurance Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of March 19 60

My commission expires February 5, 1964

Sara Wimberly  
Sara Wimberly Notary Public.

O. A. Sutton, Stauffer #1

SW SW NW Sec. 11-23S-2W  
Harvey County, Kansas

Commenced - 3-7-60

Completed - 3-17-60

Casing - 206' - 10 3/4" Surface Csg. w/200 sacks Cement

Elevation - 1435 KB

DRILLERS LOG

0 - 75	Clay
75 - 206	Shale and Lime
206 - 390	Shale and Shells
390 - 490	Lime
490 - 605	Lime
605 - 865	Lime
865 - 1120	Lime
1120 - 1495	Shale w/lime stks.
1495 - 1854	Shale and Lime
1854 - 2020	Lime and Shale stks.
2020 - 2300	Lime and Shale
2300 - 2500	Shale and Lime
2500 - 2588	Lime
2588 - 2640	Lime (KC)
2640 - 2750	Lime
2750 - 2845	Lime
2845 - 2945	Lime
2945 - 2990	Lime
2990 - 3027	Miss
3027 - 3080	Miss
3080 - 3100	Miss
3100 - 3144	Miss
3144 - 3182	Miss
3182 - 3205	Miss and Shale
3205 - 3358	Shale and Lime
3358 - 3384	Viola
3384 - 3392	Simp
3392 - 3417	T.D.

STATE OF KANSAS )  
                          ) SS  
SEDGWICK COUNTY )

I, the undersigned, being duly sworn on oath, state that the above Drillers log is true and correct to the best of my knowledge and belief and according to the records of this office.

J. S. SUTTON & SONS DRILLING CO.

By X *[Signature]*

Subscribed and sworn to before me this 22nd day of March, 1960.

*[Signature]*  
Notary Public

My Commission expires February 27, 1961.