

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-079-20364-00-00

LEASE NAME Hairy

WELL NUMBER 3

330 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 11 TWP. 23 RGE. 2 (E) or (W)

COUNTY Harvey

Date Well Completed NA

Plugging Commenced 3-25-02

Plugging Completed 3-25-02

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Bear Petroleum, Inc.

ADDRESS P.O. Box 438, Haysville, KS 67060

PHONE# (316) 524-1225 OPERATORS LICENSE NO. 4419

Character of Well Oil

(Oil, Gas, O&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 3-4-02 (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? no

Producing Formation Mississippi Depth to Top 2942 Bottom 2977 T.D. 2977

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	Surf	229	8 5/8	229	0
	Production	Surf	2978	5 1/2	2978	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Dumped sand from 2968' to 2892', dump 5 sack cement on sand, perf 525' and 279', run poly pipe to 525', spot 35 sack, let cement set up, pull poly to 279', circulate 100 sack cement to surface, pull poly, and top well off. Ran 110' of poly pipe and topped well off with 30 sack cement.

Name of Plugging Contractor Gressel Oil Field Service, Inc. License No. 3004

Address P.O. Box 607, Burrton, KS 6702C

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bear Petroleum, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss. **KCC WICHITA**

R. A. Schremmer

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 438, Haysville, KS 67060

SUBSCRIBED AND SWORN TO before me this 30th day of March, 19 2002

Shannon Howland

Notary Public

My Commission Expires: 3-10-04

SHANNON HOWLAND
 Notary Public - State of Kansas
 My Appt. Expires 3/10/04

Form CP-1
 Revised 05-88

OR