


15-185-00511-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



STAFFORD County. Sec. 25 Twp. 24 Rge. 13 (X) W(W)
Location as "NE/CNW&SW&" or footage from lines NE SE SW
Lease Owner PETROLEUM, INC.
Lease Name FOX Well No. 1
Office Address ROUTE 2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed January 17, 1958
Application for plugging filed January 18, 1958
Application for plugging approved January 21, 1958
Plugging commenced January 17, 1958
Plugging completed January 17, 1958
Reason for abandonment of well or producing formation
No Produccible Zones
If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, 222 S.Main, St. John, Ks.
Producing formation ----- Depth to top --- Bottom --- Total Depth of Well 4170' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	280'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud up with heavy mud to 250' pushed down 1/2 sack hulls to 250' followed by wooden plug. Placed 20 sacks cement through drill pipe on to plug. Mud up to 35' and placed 1/2 sack hulls at 35' followed by wooden plug. and 10 sacks cement to base of well cellar.

1-31-1958
STATE CORPORATION COMMISSION
JAN 31 1958
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
Don Searle (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
ROUTE 2, GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of January, 1958
My commission expires July 11, 1960
Notary Public.

PLUGGING
FILE SEC 25 T 24 R 13 W
BOOK PAGE 47 LINE 19

WELL LOG

15-185-00511-0000

COMPANY, PETROLEUM, INCORPORATED

24S
SEC. 25 T. ~~24~~ R. 13W

FARM FOX NO. 1


LOC. NE, SE, SW

TOTAL DEPTH 4170'

COUNTY STAFFORD, KANSAS

COMM. January 5, 1958 COMP. January 17, 1958

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 280' W/250 sax.

ELEVATION ~~1909~~ 1909' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

50	Surface clay & sand
740	Shale & sand
750	Anhydrite
1100	Red bed
1230	Shale
1760	Shale & shells
2200	Lime & shale
2410	Shale & shells
2615	Shale
3648	Shale & lime
3690	Lime
3750	Cherty lime
3805 =	Lime
3864	Lime & chert
3905	Lime
3965	Shale & lime
4021	Lime & chert
4050	Lime
4060	Lime & shale
4110	Lime
4125	Lime & sand
4170	Lime & shale
4170	T. D.

1-31-58

State of KANSAS }
County of BARTON } ss:

PLUGGING	
FILE	SEC. 25 T. 24 R. 13W
BOOK	PAGE 77 LINE 19

I, VERNE A. MORRIS of GARVEY DRILLING CO.

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 FOX well

Verne A. Morris

Subscribed and sworn to before me this 28th day of January 19 58

My Commission Expires: July 11, 1960

John T. Brown
NOTARY PUBLIC