

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

**Give All Information Completely
Make Required Affidavit**

Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR

Strike out upper line when reporting plugging off formations.

FORMATION PLUGGING-RECORD

NORTH

Locate well correctly on above
Section Plat

Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH

Stafford County. Sec. 25 Twp. 24S Rge. (E) 13 (W)
 Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. Gen. W $\frac{1}{2}$ SW $\frac{1}{4}$ NW $\frac{1}{4}$
 Lease Owner. Aladdin Petroleum Corp.
 Lease Name. Henderson Well No. 1
 Office Address. Petroleum Building, Wichita, Kansas.
 Character of Well (completed as Oil, Gas or Dry Hole). Dry
 Date well completed. December 19, 1949
 Application for plugging filed. 19
 Application for plugging approved. 19
 Plugging commenced. December 20, 1949
 Plugging completed. December 20, 1949
 Reason for abandonment of well or producing formation. Dry

If a producing well is abandoned, date of last production.....19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well..... C. D. Stoen, Great Bend, Kans.

Producing formation..... Depth to top..... Bottom..... Total Depth of Well 4240 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Hole filled with mud to top, pushed three limbs and wood plug cross wise on top of plug, then 2 burlap sacks on top of plug, pushed plug to 250', mixed 15 sacks cement in barrel, put in hole through drill pipe for lower plug, hole bridged at 40' from top of ground with tree limbs, burlap sacks and crushed rock to 30' from top, no fluid above rock. Mixed 10 sacks cement in barrel, put in through surface pipe to bottom of cellar for top plug.

12-28-49

~~DEC 28 1949~~

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....**Aladdin Petroleum Corp.**
Address.....**Petroleum Building - Wichita, Kansas.**

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
N. W. Aylward (employee of owner) or (~~owner or operator~~) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. W. Cleveland

410 E 4th St Herington Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of December 1942

My commission expires..... July 9, 1952.

22-2625 2-48-15M

Notary Public.

PLUGGING
FILE SEC 25 T 24 R 136
BOOK PAGE 131 LINE 6

HENDERSON WELL #1

Casing Record:	COMPANY	ALADDIN PETROLEUM CORP.	Description:
8-5/8" Casing - 452'	CONTRACTOR:	AYLWARD DRILLING CO.	Gen. W $\frac{1}{2}$ SW $\frac{1}{4}$ NW $\frac{1}{4}$
	COMMENCED:	December 4, 1949	Section 25-24-13
	COMPLETED:	December 19, 1949	Stafford Co., Kansas
			Elevation:
			Potential: D. & A.

Formation	From:	To:	Remarks:
Sand	0	150	
Shale Red	150	330	
Shale	330	452	8" Casing set at 452' and cemented with 200 Sax.
Red Bed and Shale	452	760	
Anhydrite	760	785	
Shale and shells	785	1770	
Lime and shale	1770	1810	
Lime Sandy	1810	1915	
Lime	1915	2160	
Lime and shale	2160	2430	
Shale and shells	2430	2790	
Shale	2790	2870	
Lime and shale	2870	2975	
Shale and shells	2975	3105	
Lime	3105	3325	
Lime and shale	3325	3395	
Lime	3395	3495	
Shale	3495	3595	
Lime	3595	3634	
Lime Broken	3634	3665	
Lime	3665	3733	
Lime and shale	3733	3995	
Cherty Conglomerate	3995	4070	
Cherty Shale	4070	4085	
Cherty Lime and shale	4085	4135	
Conglomerate	4135	4180	
Sand, Chert and slate	4180	4220	
Lime	4220	4240	
	T.D.	4240	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

Al Skalsky
Al Skalsky

Subscribed and sworn to before me this 22nd day of December, 1949. DEC 28 1949

Flora Cooper
NOTARY PUBLIC

My Commission Expires
July 16, 1952.

