


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 26 Twp. 24 Rge. 13 (X) (W)
Location as "NE/CNW/SW" or footage from lines SW/4 NE/4 NW/4
Lease Owner Falcon Drilling Company, Inc.
Lease Name Allender Well No. 1
Office Address 300 Schweiter Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 1 19 60
Application for plugging filed December 1 19 60
Application for plugging approved December 1 19 60
Plugging commenced December 1 19 60
Plugging completed December 1 19 60
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Depth to top Bottom Total Depth of Well 4170 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|--------------|---------|------|------|-------|--------|------------|
| Surface Pipe | | 0 | 246' | 8 5/8 | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole with heavy drilling mud to 235', set plug, 1/4 sack hulls on plug and 20 sacks cement. Fill hole with heavy drilling mud to 35', set plug, 1/4 sack hulls on top of plug, and 10 sacks of cement. Put 3 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

DEC 7 1960 12-7-60

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Don Gardner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
300 Schweiter Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of December, 19 60

My commission expires 1-14-64

[Signature]
Notary Public.



DRILLER'S LOG

OPERATOR: Falcon Drilling Company, Inc.
 CONTRACTOR: Falcon Drilling Company, Inc.
 300 Schweiter Building
 Wichita, Kansas
 LEASE: Allender
 WELL: No. 1
 LOCATION: SW NE NW Section 26, Township 24 South,
 Range 13 West, Stafford County, Kansas
 DATE COMM: November 21, 1960
 DATE COMPL: December 1, 1960
 CASING: Set 8 5/8" @ 246 with 200 sacks cement

| <u>FROM</u> | <u>TO</u> | |
|-------------|-----------|----------------------------|
| 0 | 246 | Surface hole |
| 246 | 765 | Shale & Red Bed |
| 765 | 790 | Anhydrite |
| 790 | 3605 | Lime & Shale |
| 3605 | 3980 | Lime |
| 3980 | 4030 | Viola Shale - Lime & Chert |
| 4030 | 4055 | Viola |
| 4055 | 4110 | Viola-Lime-Chert |
| 4110 | 4160 | Simpson-Arbuckle |
| 4160 | 4170 | Lime |
| 4170 | T.D. | |

RECEIVED
 STATE GEOLOGICAL COMMISSION
 DEC 7 1960
 CONSERVATION DIVISION
 Wichita, Kansas
 12-7-60

I certify the above to be true and correct to the best of my knowledge and belief.

FALCON DRILLING COMPANY, INC.

By Don Gardner
 Don Gardner

Subscribed and sworn before me this 5th day of December, 1960.

Martha Gorges
 Martha Gorges
 Notary Public

My commission expires:

December 14, 1961