


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County. Sec. 12 Twp. 27S Rge. 5 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C, NE $\frac{1}{4}$, NE $\frac{1}{4}$, NW $\frac{1}{4}$.
Lease Owner R. C. Patton Co., and Others.
Lease Name Harding Well No. 1
Office Address 612 Orpheum Bldg. Wichita 2, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 22nd, 19 49
Application for plugging filed June 21st, 19 49
Application for plugging approved June 21st, 19 49
Plugging commenced June 22nd, 19 49
Plugging completed June 22nd, 19 49
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Depth to top Bottom Total Depth of Well 4086 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	199ft.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Filled with Heavy Rotary Mud thru drill pipe to 200 feet. Bridge Plug at 200 feet Cemented with 15 Sacks of Cement. Heavy Mud to 20 feet from bottom of celler Bridge Plug and 5 sacks cement to bottom of celler.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to R. C. Patton Co.,
Address 612 Orpheum Bldg. Wichita 2, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

R. C. Patton (OWNER OR LEASEE OR operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R.C. Patton

612 Orpheum Bldg. Wichita 2, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of June, 19 49

RECEIVED [Signature] Notary Public.

My commission expires Oct. 4th 1953

Conservation Div. 9-48-10M

PLUGGING
FILE SEC 12 T 27 R 21
BOOK PAGE 10 LINE 21

JUN 23 1949
STATE CORPORATION
COMMISSION
KANSAS

R. C. Patton Co.,
Harding Well #1

Located C, NE/4, NE/4, NW/4,
Section 12, T27S, R5W,
Kingman County, Kansas.
CASING RECORD
8 5/8 Casing at 199 Ft.
Cemented with 200 Sacks Cement.

Total Depth 4086 Ft.
Comm. 6/1/49
Comp. 6/22/49
Contractor R. C. Patton Co.,

Sand	40
Red Bed	45
Shale & Shells	400
Salt & Shale	545
Shale & Shells	700
Lime	920
Lime & Shale	1320
Shale & Shells	1365
Lime & Shale	2120
Shale	2195
Lime & Shale	2250
Lime	2330
Lime & Shale	2410
Lime Broken	2820
Lime & Shale	2837
K. C. Lime	3255
Lime & Shale	3308
Gray & Red Shale	3355
Shale	3416
Lime & Shale	3463
Shale	3507
Lime & Shale	3538
Shale	3610
Shale & Lime	3638
Chert	3679
Hard Cherty Lime	3687
Cherty Lime	3735
Gray Lime	3765
Lime & Shale	3798
Lime	3829
Lime & Shale	3898
Shale	3944
Lime & Shale	3962
Shale	4008
Lime Viola	4018
Sandy Shale	4071
Lime	4086
Total Depth	4086

TOPS	
Topeka Lime	2225
Base Oread Lime	2680
Lansamg Kansas City Lime	2837
Mississippi Limd	3638
Kinderhook Shale	3898
Viola Lime	4008
Simpson Formation	4016
Arbuckle	4068

STATE OF Kansas COUNTY OF Sedgwick ss,

I, the undersigned, being duly sworn, on oath state that the above statement and log is a true and correct redord and log of the well drilled at the location above described.

R. C. PATTON CO.,

BY R. C. Patton

Subscribed and sworn to before me this 22 day of June 1949

J. P. Hendrick
Notary Public

My Commission expires Oct 4th 1953

RECEIVED
Conservation Div.

PLUGGING JUN 23 1949
FILE SEC-12 1-27-50 INFORMATION
DECK PAGE 02 UNIT 01 KANSAS