

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas. 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-081-20,201-00-00

LEASE NAME KOEHN "A"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1
1250 Ft. from S Section Line

4030 Ft. from E Section Line

LEASE OPERATOR TXO Production Corp.

SEC. 12 TWP. 28S RGE. 32E (W)

ADDRESS 200 W. Douglas, Suite 300, Wichita, KS 67202

COUNTY Haskell

PHONE# (316) 265-9441 OPERATORS LICENSE NO. 5171

Date Well Completed 6-28-85

Character of Well D & A

Plugging Commenced 6-28-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-28-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? unknown

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation N/A Depth to Top _____ Bottom _____ T.D. 3400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	806'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Spotted 1 sk hulls & 30 sxs Class 'H' cmt @ 2371'. Pumped plug to perfs @ 2486-90'. Spotted 50 sxs cmt @ 780', 50 sxs @ 830', 10 sxs @ 150', 10 sxs @ 40'. Cmt dropped to 200'. Pumped 140 sxs cmt down surface pipe @ 400#, 5"=0. Job completed @ 1:30 pm on 6-28-85.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Patrick Well Service License No. -

Address 852 Petroleum Rd, Liberal, KS

STATE OF _____ COUNTY OF _____, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jerry W. Collins

(Address) Jerry W. Collins
200 W. Douglas, Suite 300

SUBSCRIBED AND SWORN TO before me this 5th day of August, 19 85

Connie F. Koehler

Notary Public
STATE CORPORATION COMMISSION

My Commission Expires: July 10, 1988

Connie F. Koehler
NOTARY PUBLIC
State of Kansas
MY APPT. EXPIRES 7/10/85

SEP 13 1985
9-13-85
CONSERVATION DIVISION

Form CP-4
Revised 08-84