


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Hodgeman County. Sec. 7 Twp. 23S Rge. 23 (W)

Location as "NE/CNW/SW" or footage from lines. C SW SW  
Lease Owner Jones-Gebert Oil Co.  
Lease Name Litzenberger Well No. 1  
Office Address 1007 Central Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 5 19.62  
Application for plugging filed October 5 19.62  
Application for plugging approved October 5 19.62  
Plugging commenced October 5 19.62  
Plugging completed October 5 19.62  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production. 19.  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4844 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	364'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set bottom plug, 35 sx. cement @350 - 265, top plug, 20 sx. cement from 0-55 ft., 2 sx. in rat hole.

10-9-62  
RECEIVED

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Jones-Gebert Oil, Inc.  
Address 1007 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
George R. Jones (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *George R. Jones*  
1007 Central Bldg., Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 8th day of October, 1962.

My commission expires February 1, 1964

*Barbara J. Layton*  
Barbara J. Layton Notary Public.



DRILLERS' LOG

Company:	Jones-Gebert Oil Co.
Contractor:	Jones-Gebert Oil, Inc.
Farm:	Litzenberger #1
Location:	C SW SW, Sec. 7-23S-23W Hodgeman County, Kansas
Commenced:	9/20/62
Completed:	10/5/62
Casing:	364' of 8-5/8" w/225 sx.

0	-	162	Surface
162	-	362	Surface
362	-	620	Sand and shale
620	-	1008	Sand and shale
1008	-	1615	Shale and red bed
1615	-	1851	Sand, shale & lime streaks
1851	-	2069	Lime, sand, shale, red bed
2069	-	2353	Red bed and shale
2353	-	2495	Lime and shale
2495	-	2615	Shale, lime and red bed
2615	-	2685	Red bed and shale
2685	-	2810	Shale and lime
2810	-	2881	Shale and Ft. Riley
2881	-	2955	Ft. Riley lime
2955	-	3070	Lime and shale
3070	-	3192	Shale, lime and chalk
3192	-	3290	Shale, lime and chalk streaks
3290	-	3432	Lime, chalk and shale
3432	-	3502	Lime and shale
3502	-	3614	Lime and shale
3614	-	3737	Lime, shale and chalk streaks
3737	-	3814	Lime, shale and chalk
3814	-	3934	Lime, shale and chalk streaks
3934	-	3981	Lime and shale
3981	-	4077	Chalk streaks, shale and lime
4077	-	4128	Lime and shale streaks
4128	-	4173	Lime and shale
4173	-	4235	Lime and shale
4235	-	4296	Lime and chalk
4296	-	4298	Lime and chalk
4298	-	4358	Lime, shale and chalk
4358	-	4424	Lime and shale
4424	-	4458	Lime and shale streaks
4458	-	4525	Lime, shale and chalk
4525	-	4595	Lime and shale
4595	-	4613	Lime and chert
4613	-	4680	Lime, chert, shale and chalk
4680	-	4703	Lime, chert and shale

Drillers' Log  
Page -2-


4703	-	4760	Lime, chert and shale
4760	-	4785	Chert, lime and shale
4785	-	4844	Lime and chert
4844	-		Rotary Total Depth

I, George R. Jones, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Litzenger, C SW SW, Sec. 7-23S-23W, Hodgeman County, Kansas, as reflected by the files of Jones-Gebert Oil, Inc.

*George R. Jones*  
George R. Jones

State of Kansas            )  
                                          ) ss:  
County of Sedgwick        )

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas this 8th day of October, 1962.



My commission expires:  
February 1, 1964

*Barbara J. Layton*  
Barbara J. Layton, Notary Public

INDEXED  
SERIALIZED  
OCT 10 1962  
FBI - WASH DC