

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Hodgeman SEC. 11 TWP. 23S RGE. 24W E/W
Location as in quarters or footage from lines:
.800' FSL 520' SWL NW 1/4

Lease Owner American Energies Corporation
Lease Name Mack #1 Well No. _____
Office Address 575 Fourth Financial Center Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 5-1-82
Plugging completed 5-5-82
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom T.D. 4565'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	385'	none
				4-1/2"	4564'	3435'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

~~Plugged off bottom with sand to 4500' and ran 4 sacks cement. Shot casing @3815',
3605' and 3435'. Pulled a total of 82 joints of 4-1/2" casing. Squeezed hole with
5 sacks gel, 3 sacks hulls, 10 sacks gel, 70 sacks cement. 1 sack hulls, 15 sacks gel,
released plug and displaced with 70 sacks cement.~~

~~Plugging Complete.~~


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 176 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of May, 19 82



My Commission expires:

Irene Hoover
Notary Public
MAY 13 1982
5-13-82
CONSERVATION DIVISION
Wichita, Kansas