

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-083-21,27200-00

LEASE NAME MACK

WELL NUMBER B #1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

2970 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 11 TWP. 23 RGE. 24 (E) or (W)

COUNTY HODGEMAN

Date Well Completed _____

Plugging Commenced 12-28-93

Plugging Completed 12-28-93

LEASE OPERATOR APACHE DRUGS CO., INC.

ADDRESS P.O. BOX 454 NESS CITY, KS. 67560

PHONE (913) 798-3995 OPERATORS LICENSE NO. 6455

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-22-93 (date)

by STEVE MEDDLETON (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? _____

Producing Formation MISSISSIPPI Depth to Top 4621' Bottom 4635' D. 4660'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
DAKOTA	WATER	0'	473'	8 5/8"	473'	NDNE
MISSISSIPPI	OIL	4621'	4635'	4 1/2"	4660'	2250'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Shot casing off at 2200', pull 16 jts. to 1550' and pumped 50 sacks 60/40 pos. to 90 gel and 10 sacks gel spacer. Pull 26 jts. of casing to 525' and pumped 30 sacks and 4 sacks gel spacer. Pull rest of casing and fill to surface with cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PLAINS, INC. License No. 4072

Address P.O. BOX 346 NESS CITY, KS. 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: APACHE DRUGS CO., INC. 1-6-94

STATE OF KANSAS COUNTY OF NESS, ss. 1-6-94

NET BASE (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) _____

CONNIE J. BASE
 NOTARY PUBLIC
 STATE OF KANSAS
 My Appt. Exp. 5-5-94
 My Commission Expires: 5-5-94

AND SWORN TO before me this 5th day of January, 19 94

Connie J. Base
 Notary Public