

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-083-21153-00-00
API NUMBER

LEASE NAME Tracy

WELL NUMBER 1

SPOT LOCATION SW/SE/NW

SEC. 12 TWP. 235 RGE. 24 (S) or (N)

COUNTY Hodgeman

Date Well Completed 7-22-84

Plugging Commenced 7-22-84

Plugging Completed 7-23-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Gruss Petroleum Mgmt. Corp.

ADDRESS %Petroleum Technical Services Company
3000 N. Garfield, Ste. 210
Midland, Texas 79705

PHONE # (915) 684-6603 OPERATORS LICENSE NO. 9726

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Verbal approval obtained 7-21-84

Which KCC/KDHE Joint Office did you notify? Wichita, Kansas

Is ACO-1 filed? If not, is well log attached? Yes

Producing formation None Depth to top bottom T.O. 4631'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Dakota	Water	300'	400'	8-5/8"	515	0-cmt. circ
Lansing	"	3920'	4180'			
Cherokee	"	4490'	4560'			
Mississippian	"	4560'	T.D.			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Ran drill pipe, open ended, and spotted 50 sack cement plug from 1515' back to 1365', spotted 50 sack cement plug from 565' back to 416', spotted 10 sack cement plug from 40' to surface, filled rat hole and mouse hole with 15 sacks of cement, plugging complete at 12:00 p.m., July 23, 1984 by Halliburton. Hole loaded and plugs spotted with 9.7 PPG drilling mud.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor DNB Drilling Inc. License No. 5476

Address 515 Garvey Bldg. Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

STATE OF COUNTY OF , ss.

Don C. Bennett, Agent

~~operator~~ of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Don C. Bennett

(Address) 3000 N. Garfield, Ste. 210

Midland, Texas 79705

SUBSCRIBED AND SWORN TO before me this 31st day of July, 1984

Linda Edwards
Notary Public

My Commission expires: 3-31-85

AUG 03 1984
8-3-84
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4 1-84
Revised 06-83

State of Kansas



JOHN CARLIN
MICHAEL LENNIEN
R. C. (PETE) LOUX
PHILLIP R. DICK
JUDITH MCCONNELL
BRIAN J. MOLINE

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE SECRETARY
GENERAL COUNSEL

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

January 5, 1984

NOTICE

TO: All Operators
FROM: Duane Rankin

In keeping with the conservation practices the well plugging record has been reduced in size by reducing the form from the 8½" X 14" legal size to a standard size 8½ X 11" sheet.

The only other changes in the form are the addition of the KAR number and the time the form is to be submitted to the Conservation Division in Wichita, Kansas.

Please stop using the large form as soon as possible. You may request additional forms by calling or writing to the Conservation Division.

bgt