

15-095-00202-0000

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

Kingman County. Sec. 22 Twp. 27 Rge. 5<sup>W</sup> (E) (W)  
Location as "NE/CNW&SW" or footage from lines. SW SW SW  
Lease Owner Bankoff Oil Co.  
Lease Name Diffenbacher Well No. 1  
Office Address Drawer 2479, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 19  
Application for plugging filed January 26 19 59  
Application for plugging approved January 26 19 59  
Plugging commenced January 26 19 59  
Plugging completed January 31 19 59  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampell  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3818 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled back with sand to 3775' 5 sacks cement  
Shot casing at 3228'-3165'  
Shot casing 3102' pulled 85 jts.  
Pulled 13 jts squeezed hole with 25 sacks cement  
mud plug and 50 sacks cement  
filling surface casing from 150' to base of cellar with cement  
Per State Corporation Commission orders

RECEIVED  
STATE CORPORATION COMMISSION

FEB 4 1959

2-4-59

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.  
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Roy L. Myers, Secretary-Treasurer  
Box 364, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 3 day of February, 1959

My commission expires December 18, 1962

Notary Public.

PLUGGING  
FILE SEC. 22 T. 27 R. SW  
BOOK PAGE 12 LINE 33

KATHY WELL #1

15-095-00202-0000

Company - Bankoff Oil Company, et al.  
Contractor - Smitherman & Cohen Drilling Co.  
Farm Name - Diefenbacher

Location:  
SW SW SW, Sec. 22-27S-5W,  
Kingman County, Kansas

Commenced - May 5, 1951  
Completed - May 25, 1951  
Total Depth - 3818'  
Initial Production - 10 Bbls. Oil Per Hr.

Elevation - 1491' L&S  
Casing:  
8" - 154' c/100 Sacks Bulk Cement  
5 1/2" OD - 3802' c/50 Sacks Bulk Cement

Figures Indicate Bottom of Formations

Sand and shale	163
Shale and shells	565
Shale, shells and salt	755
Line and shale	1615
Shale and line	2395
Line and shale	2675
Shale and line	3000
Line and shale	3079
Line	3160
Shale and line	3515
Line and shale	3602
Line	3712
Shale and line	3777
Miss. Chert	3815
Line	3818 T.D.

8" - 154' c/100 sacks Bulk Cement  
5 1/2" OD - X 3802' c/50 scks Bulk Cement

RECEIVED  
STATE CORPORATION COMMISSION

JAN 27 1959

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the above to be a true and correct copy of the log of Kathy Well #1

located in the SW SW SW, Sec. 22-27S-5W, Kingman County, Kansas.

Subscribed and sworn to before me this 6th day of June, 1951.

My Commission expires March 3, 1955

Notary Public

PLUGGING

FILE SEC. 22 T. 27 R. 5W

BOOK PAGE 12 LINE 33

1-24-59

FRED HAMPELL  
PRETTY PAPER