

STATE OF KANSAS  
STATE CORPORATION COMMISSION

All Information Completely  
Be Required Affidavit  
If or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County. Sec. 22 Twp. 27S. Rge. 5W (X) (W)  
Location as "NE/CNW/SW" or footage from lines SW SE SW

Lease Owner Time Petroleum Company

Lease Name Dieffenbacher Well No. 1

Office Address 813 Union National Bank, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-17-63 19

Application for plugging filed 10-17-63 19

Application for plugging approved 10-17-63 19


Plugging commenced 10-17-63 19

Plugging completed 10-17-63 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4219 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	215'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 225' Plug 1/2 sack hulls and 25 sacks cement

Mud to 40' Plug 1/2 sack hulls and 10 sacks cement with 2 sacks in rat-hole.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 22 1963

10-22-63  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address P. O. Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

R. O. Box 486, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of October, 1963

My commission expires August 17, 1965

Donald E. Hunt, Notary Public

DRILLER'S LOG

COMPANY: Time Petroleum Company  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: DIEFFENBACHER #1  
 LOCATION: SW SE SW Sec. 22-27S-5W  
 KINGMAN COUNTY, KANSAS  
 COMMENCED: 10-5-63  
 COMPLETED: 10-17-63

0	40	Surface Soil & Clay
40	110	Shale with Sand
110	700	Shale
700	1125	Lime & Shale
1125	1370	Lime
1370	1510	Lime & Shale
1510	1965	Shale & Shells
1965	2195	Shale & Lime
2195	2455	Lime & Shale
2455	2840	Lime
2840	2956	Shale
2956	3580	Lime
3580	3802	Lime & Shale
3802	3902	Lime & Chert
3902	3993	Lime
3993	4029	Lime & Shale
4029	4052	Shale & Lime & Chalk
4052	4067	Lime & Chert
4067	4159	Shale & Lime
4159	4166	Sand
4166	4198	Sand & Shale & Chert
4198	4216	Shale & Lime
4216	4219	Simpson Sand
	<u>4219</u>	<u>Rotary Total Depth - D. &amp; A.</u>

RECEIVED  
STATE CORPORATION COMMISSION

OCT 22 1963

CONSERVATION DIVISION  
Wichita, Kansas

Set 8 5/8" used surface casing @ 215' with landing joint cemented with 175 sacks GL 3.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Dieffenbacher #1 well located in SW SE SW of Section 22, Township 27 South, Range 5 West, Kingman County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS )  
                          ) SS  
COUNTY OF BARTON )

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 21st day of October, 1963.

Donald E. Hunt

Donald E. Hunt

My Commission Expires:  
August 17, 1965