


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
880 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Kingman County. Sec. 26 Twp. 27 Rge. 5 (E) (W)
Location as "NE/CNW¹/₄SW¹/₄" or footage from lines NW NW SE
Lease Owner Fred Anschutz et al
Lease Name Simons Well No. 1
Office Address Union Nat. Bank Bldg.
Character of Well (completed as Oil Gas or Dry Hole) Dry Hole
Date well completed April 21, 1950 19.
Application for plugging filed April 22, 19.50
Application for plugging approved April 21, 19.50
Plugging commenced April 21, 19.50
Plugging completed April 21, 19.50
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well D. C. Lilly
Producing formation Depth to top Bottom Total Depth of Well 4325 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
surface gravel	water	0	130	10-3/4	140	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

The hole was filled with heavy mud to 140 feet wooden bridging plug set at 140' and 15 sacks of mixed cement placed on top of it. Hole was then filled with heavy mud to 15'. Wooden bridging plug set at 15' and tied to top of surface, 10 sacks of mixed cement placed on top of it.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Fred Anschutz
Address Union National Bank Bldg. Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Allison (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Allison
715 Brown Bldg. (Address)

SUBSCRIBED AND SWORN to before me this 22nd day of April 1950.
Madelise M. Robinson Notary Public.

My commission expires July 1, 1950

PLUGGING
FILE SEC 26 T 27 R 5W
BOOK PAGE 2 LINE 6

4-24-50

15-095-00514-0000

LOCATION: NW NW SE

SEC: 26 TWP: 27 R: 5W

FARM: Simons No. 1

CASING RECORD:

10-3/4" 140'

COMPANY: Fred Anschutz etal

CONTR: A. D. Allison & Co., Inc.

COMM: 4/5/50 COMP: 4/21/50

PROD: dry

FORMATION	DEPTH
sand and red rock	130
shale and shells	140
red rock	200
shale and shells	340
shale and salt	790
anhydrite	850
shale and shells	1055
lime and shale	1280
lime	1455
lime and shale	1695
lime and shale	2420
lime	3498
shale	3530
lime	3615
shale	3769
lime	4029
shale	4178
lime	4228
shale	4260
shale and sand	4298
dolomite	4325

TOTAL DEPTH: 4325

TOPS:

Lansing-Kansas City	2955
Mississippian	3770
Viola	4174
Simpson dolomite	4184
Simpson sand	4185
Arbuckle dolomite	4298
Excellent porosity no stain	4306-15

DST:

3800-3814
Recovered 94' slightly oil and gas cut mud in one hour
3809-3835
Recovered 360' slightly gas cut mud in one hour.

Certified true copy of drillers log.

BY

J. Allison

PLUGGING
FILE SEC 26 T 27 R 5W
PAGE 2 LINE 6

REC
APR 24 1950
STATE OF KANSAS