

1 050714

API NUMBER 15- 185-22,318-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

W/2 NW SE, SEC. 20, T 24 S, R 13 (W/KX)

1980 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5030

Lease Name Claycomb Well # 1

Operator: PV Properties, Inc.
Name & Address: 400 North Woodlawn, Suite 101
Wichita, KS 67208

County Stafford 135.69

Well Total Depth 4175 Simpson feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 363

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor L D Drilling, Inc. License Number 6039

Address R. R. 1, Box 183-B, Great Bend, KS 67530

Company to plug at: Hour: 12:45 pm Day: 10 Month: December Year: 19 85

Plugging proposal received from Don Pope

(company name) L D Drilling (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1930 Est. Anhydrite 811-37'

1st plug at 4150' with 30 sx cement (if in Arbuckle 50' or more)

2nd plug at 800' with 50 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement solid bridge -

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:00 pm Day: 10 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 800' with 50 sx cement; 2nd plug at 400' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement. Plugged water well with 5 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. (if additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 18 1985

INV. NO. 11604

RECEIVED STATE CORPORATION COMMISSION

DEC 16 1985

Signed Richard W. Lacey (TECHNICIAN)

CONSERVATION DIVISION Wichita, Kansas

12-16-85