

**STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION**

FORM CP-1

Rev. 03/92

130 S. Market, Room 2078
Wichita, Kansas 67202

RECEIVED
 KANSAS CORP COM
 1997 APR 30 4:11:23

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-095-2172100000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR: Griggs Oil, Inc. KCC LICENSE # 5058
(owner/company name) (operator's)

ADDRESS: One Main Place, 100 N. Main, #1010 CITY: Wichita
STATE: Kansas ZIP CODE: 67202 CONTACT PHONE: (316) 267-7779
LEASE: Boswell WELL#: 1-20 Section 20 Township 27s Range 9w
C N/2 SW SPOT LOCATION/QQQQ COUNTY: Kingman
1980 FEET (in exact footage) FROM S / N (circle one) LINE OF SECTION (NOT Lease Line)
1320 FEET (in exact footage) FROM E W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: Oil Well _____ Gas Well _____ D&A XX SWD/ENHR WELL _____ Docket # _____
CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS
SURFACE CASING SIZE 8-5/8" SET AT 213 KB CEMENTED WITH 165 SACKS
PRODUCTION CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
ELEVATION 1717 G.L. 1726 K.B. T.D. 2425 P.B.T.D. _____ Anhydrite Depth _____
(Stone Corral Formation)

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING:
Heavy mud to 1400' then 35 sacks, heavy mud to 900' then 35 sacks, heavy mud to 260' then 35 sacks
then heavy mud to 60' then 25 sacks. Using 60/40 Poz with 6% Gel. Plug rathole with 15 sacks and
plug mousehole with 10 sacks.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)
If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Name: Vaughn Thompson/Steve E. McClain Phone#: (316) 672-9508
Address: P.O. Box 1006 City: Pratt State: Kansas

PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142
(company name) (contractor's)
Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 6:00 pm on April 17, 1997.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent _____

DATE: 04/29/97 AUTHORIZED OPERATOR OR AGENT: _____
(signature) Steve E. McClain, Agent for Operator