

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-01003-00-01
Spot: NENWSE Sec/Twnshp/Rge: 34-17S-8W
2321 feet from S Section Line, 1803 feet from E Section Line
Lease Name: EDWARDS Well #: 2
County: ELLSWORTH Total Vertical Depth: 3600 feet

Operator License No.: 6988
Op Name: SMITH, RICHARD E. DBA SMITH OIL O
Address: 410 N. ADAMS PO BOX 550
HUTCHINSON, KS 67504

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3590		125 SX
SURF	8.625	228		200 SX
SURF		230		

Well Type: SWD UIC Docket No: D23371.0 Date/Time to Plug: 02/17/2016 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: AS PER KCC RULES & REGS. CP-1 INDICATES CASING LEAK AT 240' TO 280'.

Plugging Proposal Received By: JEFF KLOCK Witness Type: NONE
Date/Time Plugging Completed: 02/17/2016 11:45 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SWD WITH POLYMER THAT HAD FAILED MIT. PULLED TUBING AND PACKER OUT, FOUND HOLE IN PACKER & SOME TUBING. SANDED OH TO 3260' AND CAPPED WITH 5 SX'S CEMENT. CEMENT BOND LOG WAS DONE - FOUND SCATTERED CEMENT UP ABOVE 2900'. PERFORATED AT 1100', 200', AND 30'. RUN TUBING AND PACKER TO 1100' AND PUMPED 35 SX'S WITH 3% CC, CIRCUALTED CEMENT OUT OF SURFACE CASING. PULLED TUBING AND PACKER OUT, LET SET FOR 1.5 HOURS. TAGGED CEMENT AT 900'. RUN TUBING TO 850' AND PUMPED 35 SX'S COMMON CEMENT WITH 3% CC, PULLED TUBING UP TO 250' AND CIRCUALTED CEMENT UP BOTH CASINGS. PULLED TUBING OUT AND TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
3590	3600	OH	

Remarks: COPELAND TICKET #43682.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

KCC WICHITA

FEB 22 2016

RECEIVED

Form CP-2/3

no
3-2-16
CC-Mie

JK