

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-23800-00-00
Spot: SWNESE Sec/Twnshp/Rge: 3-35S-10W
2124 feet from S Section Line, 332 feet from E Section Line
Lease Name: STEPHANIE Well #: 2-3 SWD
County: BARBER Total Vertical Depth: 6585 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5555		
COND	20	80		WITH 12 SX CMT
PROD	7	5572	1996	WITH 325 SX CMT
SURF	9.625	965		WITH 630 SX CMT

Well Type: SWD UIC Docket No: D30972.0 Date/Time to Plug: 02/23/2016 2:00 PM
Plug Co. License No.: 35019 Plug Co. Name: PERMIAN WELL SERVICE LLC
Proposal Rcvd. from: CODY ROSE Company: SANDRIDGE EXPLORATION & PR Phone: (400) 590-2362

Proposed Plugging Method: SET CIBP @ 5520' & 10 SX CMT. LOAD HOLE WITH DRILLING MUD. PLUG AT 1000' WITH 100 SX CMT. PLUG AT 300' TO SURFACE WITH CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/24/2016 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 5555' & SPOTTED 10 SX CMT ON TOP OF CIBP TBROUGH TBG. LOAD HOLE WITH DRILLING MUD. 1ST PLUG CUT OFF STUB AT 1996' WITH 50 SX CMT. 2ND PLUG AT 1010' WITH 100 SX CMT. SDON TO LET CMT SET. 2/24/16: TAG TOC @ 792'. 3RD PLUG CIRCULATED CMT FROM 290' TO SURFACE WITH 99 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5572	6585		

KCC WICHITA
FEB 29 2016
RECEIVED

KCC WICHITA
FEB 29 2016
RECEIVED

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED CLASS C CEMENT BY EXCEL CEMENTING SERVICES.

Plugged through: TBG

District: 01

Signed

Stephanie Pfeifer
(TECHNICIAN)

RECEIVED
FEB 25 2016
KCC DODGE CITY

3/2/16
no
cc-UIC