

T.S. 1 031038  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

10-17  
API NUMBER 15-083-21,331-0600  
SW NW SE, SEC. 2, T 23 S, R 24 W/E  
1650 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6331 & 5146

Lease Name Martens Well # 1

Operator: Taurexco, Inc. & Rains & Williamson  
Name & Address: 125 North Market, Suite 1210  
Wichita, KS 67202

County Hodgeman 151.13

Well Total Depth 4650 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 455

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rains & Williamson Oil Company, Inc. License Number 5146

Address 220 West Douglas, Suite 435, Wichita, KS 67202

Company to plug at: Hour: 7:30 p.m. Day: 17 Month: 10 Year: 19 89

Plugging proposal received from Louis Borges

(company name) Rains & Williamson Oil Company, Inc. (phone) 316-265-9686

were: to fill hole with heavy mud and spot cement through drill pipe

- 1st plug at 1540' with 50 sx cement, 2nd plug at 870' with 50 sx cement,
- 3rd plug at 470' with 40 sx cement,
- 4th plug at 40' with 10 sx cement,
- 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9:30 p.m. Day: 17 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 1540' with 50 sx cement,

- 2nd plug at 870' with 50 sx cement,
- 3rd plug at 470' with 40 sx cement,
- 4th plug at 40' with 10 sx cement,
- 5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 19 1989  
10-19-89  
CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.  
(if additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

Signed Steve Durrant (TECHNICIAN)

DATE 10-24-89

INV. NO. 26202