

1 120870

12-28

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,272-00-00
SW SW NE, SEC. 11, T 23 S, R 24 W 4E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6455

2970 feet from S section line
2310 feet from E section line

Operator: Apache Drilling Co., Inc.

Lease Name Mack Well / B-1

Name & Address

County Hodgeman

P.O. Box 454

Well Total Depth 4660 151.45 feet

Ness City, KS 67560

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 473

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Plains Inc. License Number 4072

Address P.O. Box 346, Ness City, KS 67560

Company to plug at: Hour: 10:30 a.m. Day: 28 Month: 12 Year: 1993

Plugging proposal received from Clint Base

(company name) Plains Inc. (phone) 913-798-3995

logs: 4 1/2" at 4659' w/125 sx cement, PBD 4640', Perfs at 4621-29, 4633-35'

1st plug set CIBP at 4575',

2nd plug test casing to 300 psi. Perforate casing at 650' and pump in 80 sx cement over capacity.

3rd plug hook onto backside, pump in 220 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 28 Month: 12 Year: 1993

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4570' and dump 2 sx cement on top

2nd plug spotted 50 sx cement at 1500' through 4 1/2" casing, gel from 1300'

3rd plug spotted 80 sx cement at 525', gel from 225-40',

4th plug spotted 10 sx cement from 40-0'.

RECEIVED
STATE CORPORATION COMMISSION
JAN 04 1994
1-4-94
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
1 (1) / (XXXXXX) observe this plugging.

Signed Duane Rankin (TECHNICIAN)

DATE 1-7-94

INV. NO. 39642