

1 051347

8-15

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-083-21,343-00-00

SW NE SE, SEC. 11, T 23 S, R 24 WKE

1650 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30211

Lease Name Jones Well # 1

Operator: Coats & Malone, Inc.

County Hodgeman 152.75

Name &

Address 1007 E. 2nd

Well Total Depth 4700 feet

Wichita, KS 67214

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 402

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Company License Number 5929

Address 310 W. Central, #117, Wichita, KS 67202

Company to plug at: Hour: 6 p.m. Day: 15 Month: 8 Year: 19 90

Plugging proposal received from Duane Chisholm

(company name) Duke Drilling Company (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1564-95'

1st plug at 1590' with 50 sx cement, 2nd plug at 800' with 80 sx cement,

3rd plug at 430' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:15 p.m. Day: 15 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1590' with 50 sx cement,

2nd plug at 800' with 80 sx cement,

3rd plug at 430' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied

(If additional description is necessary, use BACK OF this form.)

INVOICED

DATE: 8-29-90

INV. NO. 29152

RECEIVED
STATE CORPORATION COMMISSION
OCT 24 1990
SOLICITATION DIVISION (TECHNICIAN)
Wichita, Kansas