

1060197

TO: STATE CORPORATION COMMISSION

API NUMBER 15-083-21,117A-0001
NE SW NW SEC. 12, T 23 S, R 24 W

CONSERVATION DIVISION - PLUGGING SECTION 3630 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4290 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME TRACY WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY HODGEMAN

153.50

OPERATOR LICENSE # 5104

WELL TOTAL DEPTH 4723 FEET

OPERATOR: BLUE GOOSE DRILLING COMPANY PRODUCTION CSG: SIZE 5 1/2" @ 4701' WITH 125 SX

NAME AND PO BOX 1413 SURFACE CASING: SIZE 8 5/8" @ 463' WITH SX

ADDRESS GREAT BEND, KS 67530-1413

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SWIFT SERVICES, INC LICENSE NUMBER 32382

ADDRESS PO BOX 466, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 4:15 PM DAY: 09 MONTH: 02 YEAR: 2000
HOUR: 4:00 PM DAY: 22 MONTH: 02 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) SWIFT SERVICES, INC (PHONE) 785-798-2300

WERE: PERFS AT 4575-76

BOTTOM PLUG PUMPED 35 SX CEMENT TO BOTTOM THROUGH TUBING. PERFORATED AT 660'. PUMPED 140

SX CEMENT ON VACUUM. WENT DOWN BACKSIDE WITH 75 SX CEMENT. PRESSURED TO 450#. SHUT IN

WITH 400#. PUMPED 75 SX CEMENT WITH 200# HULLS DOWN CASING. FLUID WENT DOWN ABOUT 600'.

Still on vacuum

ON 02/22/00 TOP OF CEMENT AT 1020'. PUMP 90 SX CEMENT FROM 1020' TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE

OPERATIONS COMPLETED: HOUR: 5:15 PM DAY: 09 MONTH: 02 YEAR: 2000
HOUR: 5:20 PM DAY: 22 MONTH: 02 YEAR: 2000

ACTUAL PLUGGING REPORT

BOTTOM PLUG PUMPED 35 SX CEMENT TO BOTTOM THROUGH TUBING. PERFORATED AT 660'. PUMPED 140

SX CEMENT ON VACUUM. WENT DOWN BACKSIDE WITH 75 SX CEMENT. PRESSURED TO 450#. SHUT IN

WITH 400#. PUMPED 75 SX CEMENT WITH 200# HULLS DOWN CASING. FLUID WENT DOWN ABOUT 600'

Still on vacuum

ON 02/22/00 TOP OF CEMENT AT 1020'. PUMP 90 SX CEMENT FROM 1020' TO SURFACE.

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

RECEIVED

STATE CORPORATION COMMISSION

3-1-00
MAR - 1 2000

I (DID) OBSERVE THIS PLUGGING

DATE 3/1/00 SIGNED

Michael Maier
(TECHNICIAN)

INV. NO. 061344

FORM CP-273 WICHITA, KANSAS