

1031542

TO: STATE CORPORATION COMMISSION

API NUMBER 15-083-21,213-0001
NW SW NW SEC. 12, T 23 S, R 24 W

CONSERVATION DIVISION - PLUGGING SECTION 3630 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4950 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME TRACY SWD WELL # 2

TECHNICIAN'S PLUGGING REPORT

2/22

COUNTY HODGEMAN 150.70

OPERATOR LICENSE # 5105 5104

WELL TOTAL DEPTH 4637 FEET

OPERATOR: BLUE GOOSE DRILLING CO. PRODUCTION CSG: SIZE 4 1/2" @ 4582' WITH 100 SX

NAME AND PO BOX 1413 SURFACE CASING: SIZE 8 5/8" @ 486' WITH 250 SX

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL GAS WELL INPUT WELL INJ WELL E-24,875 D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR FRITZLER TRUCKING, INC. LICENSE NUMBER NA 31627

ADDRESS PO BOX 544 NESS CITY, KS 67560-0544

COMPANY TO PLUG AT: HOUR: 5:45 PM DAY: 22 MONTH: 02 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MIKE FRITZLER

(COMPANY NAME) FRITZLER TRUCKING, INC. (PHONE) 785-798-3641

WERE: OPEN HOLE 4582-4637. 4 1/2" CEMENTED FROM 930' TO SURFACE.

SQUEEZE CASING WITH 200# HULLS - 25 SX CEMENT - DISPLACED WITH 35 BBLs WATER AND 130 SX

CEMENT FINAL STAGE. MAXIMUM PRESSURE AT 350 PSI. SHUT IN AT 0 PSI. PRESSURE TEST 8%

ANNULUS TO 500 PSI. 1/2 BBL TO LOAD.

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 6:30 PM DAY: 22 MONTH: 02 YEAR: 2000

ACTUAL PLUGGING REPORT

SQUEEZE CASING WITH 200# HULLS - 25 SX CEMENT - DISPLACED WITH 35 BBLs WATER AND 130 SX

CEMENT FINAL STAGE. MAXIMUM PRESSURE AT 350 PSI. SHUT IN AT 0 PSI. PRESSURE TEST 8%

ANNULUS TO 500 PSI. 1/2 BBL TO LOAD.

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

DATE 2/28/00

FEB 25 2000
2.25-00

WV. NO. 06/295

CONSERVATION DIVISION
Wichita, Kansas

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Steve Durrant
(TECHNICIAN) FORM CP-2/3

(R)