

To: 1 040750 3-27  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-083-21,391-0000 79  
NW SW SE, SEC. 12, T 23 S, R 24 W XX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123  
Operator: Pickrell Drilling Company Inc.  
Name:  
Address 110 N. Market, Ste. 205  
Wichita, KS 67202

990 feet from S section line  
2310 feet from E section line  
Lease Name Jones "CC" Well # 1  
County Hodgeman 151.12  
Well Total Depth 4650 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pickrell Drilling Company Inc. License Number 5123  
Address 110 N. Market, Ste. 205, Wichita, KS 67202

Company to plug at: Hour: 11:30 a.m. Day: 27 Month: 3 Year: 19 93

Plugging proposal received from Doyle Folkerts  
(company name) Pickrell Drilling Company Inc. (phone) 316-262-8427

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1502-28'  
1st plug at 1530' with 50 sx cement, 2nd plug at 750' with 80 sx cement,  
3rd plug at 290' with 40 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Stephen J. Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1 p.m. Day: 27 Month: 3 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 1530' with 50 sx cement,  
2nd plug at 750' with 80 sx cement,  
3rd plug at 500' with 30 sx cement,  
4th plug at 290' with 40 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
APR 1 1993  
4-1-93

INVOICED  
DATE 4-2-93  
INV. NO. 37550  
3-27

Signed Stephen J. Pfeifer  
(TECHNICIAN)